TOWN OF NEW SCOTLAND PLANNING BOARD APPROVAL

ALBANY COUNTY HEALTH DEPARTMENT APPROVAL

PERC TEST AND DEEP TEST PIT INFORMATION

PERCOLATION TEST #1
#1 = 30 sec/in
#2 = 45 sec/in
#3 = 45 sec/in
#4 = 45 sec/in

TEST PIT #1
0' to 3': Dark brown, silty SAND, mostly fine sand, some silt, moist.

3' to 8': Brown, silty GRAVEL with sand, mostly silt, som fine to coarse gravel, little coarse sand, slightly moist.

Exploration terminated at 8 feet.

PERCOLATION TEST #2
#1 = 30 sec/in
#2 = 40 sec/in
#3 = 50 sec/in
#4 = 50 sec/in

TEST PIT #2
0' to 5'-6": Light orange-brown, silty GRAVEL, mostly silt, little fine to coarse gravel, few coarse sand, slightly moist. Plant roots in top 2 feet.

5'-6" to 8': Dark brown, silty GRAVEL, mostly silt, little fine to coarse gravel, little coarse sand, slightly moist. No bedrock or groundwater encountered.

Exploration terminated at 8 feet.

PERCOLATION TEST #4
#1 = 3.0 min/in
#2 = 4.0 min/in
#3 = 5.0 min/in
#4 = 5.0 min/in

TEST PIT #4
0' to 1': Dark brown, silty SAND with grave, mostly silt and fine sand, little gravel, moist, roots.

1' to 3'-6": Light orange-brown, silty GRAVEL, mostly silt, little gravel, few clay, few cobbles, slightly moist.

3'-6" to 8': Light brown, silty Gravel, mostly silt, some gravel, few coarse sand, little clay. More coarse than above, but less hard.

Exploration terminated at 8 feet.

FOR MUNICIPAL APPROVAL ONLY-NOT INTENDED FOR CONSTRUCTION

PRELIMINARY PLAT

C4

PROPOSED GRADING & UTILITY PLAN FOR
COLONIE COUNTRY CLUB ESTATES
TOWN OF NEW SCOTLAND
COUNTY OF ALBANY, STATE OF NEW YORK

FILE: 060137 | SCALE: 1"=50' | BY: MLW | CHK: DRH | DATE: 7/17/07 | 060137-G.DWG

REVISIONS

REMARKS	DATE
GENERAL REVISIONS	1/28/08
GENERAL REVISIONS	2/25/08

STATE OF NEW YORK · DANIEL R. HERSHBERG · 044226 · LICENSED PROFESSIONAL ENGINEER & LAND SURVEYOR

ALTERATION OF THIS DOCUMENT EXCEPT BY A LICENSED PROFESSIONAL ENGINEER OR LAND SURVEYOR, IS ILLEGAL

HERSHBERG & HERSHBERG
Consulting Engineers and Land Surveyors
18 Locust Street
Albany, New York 12203